### DCS of TileCal and Forward Detectors

### Luis Seabra on behalf of LIP/ATLAS DCS group



Laboratório de Instrumentação e Física Experimental de Particulas

Jornadas LIP, Braga 19 – 02 – 2016



### **Detector Control System**

- Responsible for the coherent and safe operation of the detector
- Monitor and archives the operational parameters
- Interface between operator and detector

#### LIP responsibility

- TileCal coordination, development, maintenance and continuous upgrade
  - F. Martins (coordinator), J. Campos and L. Seabra
- ALFA coordination, development, maintenance and continuous upgrade (L. Seabra)
- AFP collaboration (L. Seabra)

#### Long Shutdown 1 Upgrade NEW


- Remove limitations and improve performance from Run 1
- Upgrade of all sub-detectors (hardware and software)
- ATLAS DCS followed ATLAS wide controls in HW and SW updates
  - Server with Linux SLC6 + VM with Windows 2008 + interfaces
  - WinCC UA version
  - Migrate the old DCS projects into the new systems

# TileCal DCS

### TileCal

#### **Detector system**

- Sampling Calorimeter (steel plates and scintillating tiles)
- Readout by wavelength shifting optical fibers into PMTs
- One long barrel and two extended barrels (into 4 partitions)
- Each partition is divided into 64 independent modules



**LBA** 

## TileCal Upgrade for phase II

### **NEW**

- Phase II -> High Luminosity in LHC
- Replacement of the front-end electronics (new read-out architecture)
  - Reduce single point failures redundancy of low voltage power
- DCS data for HV distribution system will flow in parallel with physics data to sROD

#### Main developments for DCS (Ready for test beam last year)


- HV Distribution system two options under evaluation that require design/ development (OPC)
  - HV Remote Crate HV micro controlled and distribution system located in ATLAS service cavern (USA15)
  - HV\_OPTO distribution located in the calorimeter
- LV Distribution system
  - Expected new controller board → design/development of new DCS

## Forward Detectors DCS

### **ALFA** Detector

#### **Detector system**

- Detect scattered protons at small angles (µrad scale)
- Two stations on each side of the IP (240m)
- Each detector inside a Roman Pot



**PMTs** 

**Fibers** 


connectors

Fibers layers

## ATLAS Forward Proton (AFP) NEW

#### **Detector system**

- Two stations on each side of the IP (205 and 217m)
- Station near the IP -> Silicon tracker detector (SiT)
- Station far from the IP -> SiT and a Time-of-Flight detector (ToF)
- Each detector inside a Roman Pot
- Under installation/development



SiT

### Summary

- The Detector Control System provides control and monitoring of several components and ensures the safe operation of the detector contributing to good Data Quality
- The Detectors DCS here described include a large variety of different systems successfully integrated in the ATLAS detector
- LIP is the main responsible group for the TileCal and ALFA DCS and contributes to the AFP DCS systems
- •LIP participation in the sub-detectors DCS is essential for the global ATLAS DCS

### Acknowledgements





