

TPC to increase background rejection efficiency [2].

To guarantee the quality of the acquired data, the xenon inside the detector must be extremely pure and also kept very still, as the gas bubbles and ripples on the liquid surface would interfere with S1 and S2 signals. To maintain purity, xenon is continuously circulating through the purification system, with freshly purified liquid entering the detector from the bottom and slowly passing to the top to be removed for the next purification cycle. It takes approximately 2.4 days to pass all the 10 tons of xenon through the purifier. A sophisticated cryogenic system maintains the LXe inside the detector at constant temperature of -104°C to make sure that the liquid is always still and transparent.

Figure 3 – Graphical user interface for the Liquid Nitrogen system was implemented following guidelines of High Performance Human Machine Interface



The Experiment Control

The Experiment Control (EC) system of LZ behaves like the nervous system of the detector. Its role is to guarantee safety of the detector, support systems' hardware and xenon supply. This is accomplished by monitoring and controlling parameters related to LXe conditions (such as temperature, pressure and level), field cage properties and PMT HV. The LZ infrastructure is organized in different subsystems, listed below with the corresponding number of channels that are being reported to the EC.

| Detector and Xe tower | 290 | Calibration | 226 |
|---------------------------------|-----|----------------------------|-----------|
| Xe delivery and recovery | 480 | Purity monitor | 15 |
| Xe circulation and purification | 120 | Electronics Analog+Digital | 2600+1500 |
| Cryogenics | 335 | Power distribution and UPS | 78 |
| Vacuum | 284 | PMT HV | 5516 |
| Environment monitoring | 8 | Total (SURF) | 11404 |
| Water Tank | 30 | Kr removal (SLAC) | 1336 |



Figure 4 – Graphical user interface to monitor and control the PMT arrays

The LZ Experiment Control was designed as a high availability redundant system with automatic failover:

- PLC: Dual-CPU Siemens S7-400 model
- Ignition SCADA: redundant two-server configuration
- Compressors: 2 circulation + 2 recovery
- Database: continuously replicated to a mirror on surface
- Network: two physically separated 10 GB/s links
- Redundancy in all important controls and sensors

Conclusion

The LZ detector, currently in the final stage of development, is being assembled in the Davis Lab at SURF (Sanford Underground Research Facility, South Dakota, USA), at a depth of 1500m.

Figure 2 – Experiment Control functional chart, where the main elements are the PLC and the Ignition server

The Control group is one of the most vital groups for the LUX-ZEPLIN collaboration. Its mission is to ensure the safety of the detector and the LXe during operations. This group is also responsible for the operations of an independent circulation system, developed at San Francisco in SLAC, that is being used for removal of radioactive ⁸⁵Kr from LZ xenon.

The Dark Matter group at LIP is responsible for the Ignition development and maintenance (including online support for the underground team) as well as integration of non-critical subsystems into the experiment control.

References

[1] - Akerib, D. S., et al. "The LUX-ZEPLIN (LZ) experiment." Nuclear Instruments and Methods in Physics Research Section A: Accelerators, Spectrometers, Detectors and Associated Equipment 953 (2020): 163047.

[2] - Akerib, D. S., et al. "Projected WIMP sensitivity of the LUX-ZEPLIN (LZ) dark matter experiment." arXiv preprint arXiv:1802.06039 (2018).